

R

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Sedgwick County, Sec. 31 Twp. 27 Rge. 4 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines 900' N & 330' E of C

Lease Owner The Shallow Water Refining Company

Lease Name Bartholomew Unit, Tract 11 Well No. 1

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 3-8-66 19

Plugging completed 3-11-66 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Paul Turpin

Producing formation Depth to top Bottom Total Depth of Well 3737 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	181'	None
				5-1/2"	3706'	2902'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3737', sanded hole to 3725' and dumped 5 sacks of cement @ 3725' with dump bailer. Pulled 5 1/2" casing, set rock bridge @ 200' and dumped 20 sacks of cement @ 200'. Mudded hole to 30' and ran 10 sacks of cement to base of cellar.

STATE CORPORATION COMMISSION

MAR 18 1966

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE.

3-18-66

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss. Noel J. Knight

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of March, 1966

My commission expires May 20, 1968

Milton J. Volin
Notary Public.

KANSAS WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK WICHITA, KANSAS

COF

COMPANY CITIES SERVICE OIL COMPANY

SEC 31 T. 27 R. 4W

FARM Durfee "B" NO. 1

LOC. 1/4 SW NE
590' N. 350' E. of Center

Bartholomew Unit #1

TOTAL DEPTH 3737


COMM. 6-11-50

COMP. 6-26-50

CONTRACTOR R. W. Ring Drlg. Co.; Drill In: Pasco Drlg. Co.

ISSUE 2-3-51

COUNTY Sedgwick KANSAS



ELEVATION 1403 R.T.S.

PRODUCTION PMP. 208 bbls.
4% water/24 hrs.

FIGURES INDICATE BOTTOM OF FORMATIONS

Measurements taken on R.T.S.

181
shells & salt 200
shale 1315
shale & shells 2035
lime & shale 2895
lime 3285
shale 3700
lime & chert 3737
Total depth
Tops: Brown lime 2833
Base Brown lime 2841
Lansing 2872
Base Lansing 3364
Mississippi chert 3639

Steel Line Measure:

- 2706-2717
- 3573-3573
- 3630-3630
- 3703-3705
- 3728-3730

Remarks:

Rotary total depth 3721
 I.P. Pumped 208 bbls. fluid, 4% water., 24 hrs. (State Potential) (Miss. chert az.) (Pumping unit)
 No show oil 2833'; small show oil 3291-3304; no show oil 3689-94 & 3694-3716; fair show oil 3716-21; show oil 3721-24; fair show oil 3724-31 good show oil 3731-34; fair show oil 3734-37.
 Best pay 3716-37; First Free oil 3716-21.
 Hole filled up with oil from 2000 to 2900'. (Hole was loaded with 2000' water). Az. w/1000 gals., used 82 bbls. load oil.