


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Flat

Sedgwick County, Sec. 31 Twp. 27 Rge. 4W (E) (W)
Location as "NE/CNWSW" or footage from lines 990' S, 330' W of NE/cor.
Lease Owner: Maurice L. Brown
Lease Name: (Lorena #3) Bartholomew Tr. 10 Well No. 1
Office Address: Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 10
Application for plugging filed 10
Application for plugging approved 10
Plugging commenced 11/26/73 10
Plugging completed 11/30/73 10
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 10
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dewey
Producing formation Depth to top Bottom Total Depth of Well 3745 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	203	none
				5 1/2"	3721	2814'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded hole to 3726', set 5 sacks cement. Loaded hole with water, shot pipe at 2800' and pulled 88 joints. Set rock bridge at 240' and ran 5 yards ready mix.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
DEC 13 1973
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor: KMX VOTH CASING PULLING
Address: CHASE, KANSAS

12-13-73

STATE OF KANSAS, COUNTY OF RICE ss.
WALTER VOTH (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Walter Voth
CHASE, KANSAS
(Address)

Subscribed and sworn to before me this 10th day of December 1973

Margaret Melcher
Notary Public.

My commission
MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975




Company - CITIES SERVICE OIL CO.
Farm - Lorenz No. 1

SEC. 31 T. 27 R. 24W
N^W 1/4 NE NE

330' S, 990' W of NE corner

Well Depth. 3754
Comm. 3-8-50 Comp. 3-28-50
Shot or Treated.
Contractor. R. W. Rine Drilg Co.
Issued. 9-9-50

County. Sedgwick
KANSAS



Elevation. 1415 RTE

Production. 539 bbls oil, 0 wtr.

CASING:
8 5/8" 203' cem w/150 sc.
5 1/2" 3721' cem w/150 sc.

Figures Indicate Bottom of Formations.

shale	245
sand	270
shale, shells	1100
lime, shale	2890
lime	3270
lime, shale	3704
lime, chert	3735
lime	3754

Total depth

Tops:	
Brown lime	2849
Base Brown lime	2860
Lensing lime	2870
Base Lensing lime	3369
Miss. chert	3701 ?

Rotary total depth 3745'

All measurements taken from^d. T. B.

Steel line measure:

210 = 210
500 = 500
1550 = 1550
2750 = 2756
3660 = 3660
3746 = 3745

2849, N. S. O.
2870, N. S. O.
3704-23, NSO
3723-41, SSO
3741-45, FSO
3745-49, stain
3749-51, SSO
3751-54, stain

Bailed a scum of oil and bailing indicated gas at total depth.

Best pay 3741-51.

Not shot or acidized upon completion.

RECEIVED
STATE CORPORATION COMMISSION
AUG 15 1973
CONSERVATION DIVISION
Wichita, Kansas