

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-22732-01-00
Spot: NWSWSESW Sec/Twnshp/Rge: 4-34S-4W
350 feet from S Section Line, 1550 feet from W Section Line
Lease Name: BARBARA 3404 Well #: 1-4H
County: SUMNER Total Vertical Depth: 4478 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	60		10 SX
II	7	5345	825	380 SX
PROD	4.5	8732		0 SX
SURF	9.625	476		260 SX
T1	4.5	8732		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/11/2015 12:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: STEVE JOHNSON Company: SANDRIDGE EXPL Phone: (405) 429-5000

Proposed Plugging Method: 50 SX 800', 50 SX 525'. CIRC CEMENT 250' -0'. SET CIBP @ 5400'.

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/17/2015 12:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

100 SX CLASS "C" 2% CACL THRU TUBING AT 5260'. TAGGED CEMENT AT 4855. PRESSURED TO 300' & HELD FOR 10 MINUTES. SHOT OFF 7" @ 825' PULLED & LAYED DOWN. RAN 2 7/8" TUBING TO 805' SPOTTED 50 SX CEMENT. PULLED TUBING TO 525', SPOTTED 50 SX CEMENT. PULLED TUBING TO 254' & CIRCUALTE CEMENT TO SURFACE WITH 90 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
5423	7635	CSG	

Remarks: CLASS "C" CEMENT. ORR ENTERPRISES. TMD = 8732

Plugged through: TBG

District: 02

Signed [Signature]
KCC WICHITA

(TECHNICIAN)

6/24/15 CKM

JUN 22 2015

RECEIVED