

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-23730-00-00
Spot: NENENW Sec/Twnshp/Rge: 3-10S-21W
330 feet from N Section Line, 2310 feet from W Section Line
Lease Name: RUDMAN Well #: 1
County: GRAHAM Total Vertical Depth: 3983 feet

Operator License No.: 34746
Op Name: SPIRAL ENERGY CORP
Address: 300 N MARIENFELD, STE 830
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3983		150 SX
SURF	8.625	222		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/27/2015 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: TOM BERENS Company: ALLIED CEMENT COMPANY Phone: (432) 686-2883

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 15 sx gel and 500 # hulls. DV Tool at 1781' w/450 sx cement.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/27/2015 12:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied on to casing and pumped 60 sx cement w/150 # hulls followed by 15 sx gel, followed by 165 sx cement w/250 # hulls. Tied on to backside and squeezed w/10 sx cement. Shut in pressure 200 psi. Topped off casing w/15 sx cement.

Perfs:

Top	Bot	Thru	Comments
3879			

Remarks: ALLIED CEMENT TICKET # 55773

Plugged through: CSG

6/24/15 CKM

District: 04

Signed 
(TECHNICIAN) CM

Received
KANSAS CORPORATION COMMISSION

JUN 01 2015

JUN 12 2015

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS