

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-025-21249-00-00
Spot: SWNESW Sec/Twnshp/Rge: 1-32S-24W
1415 feet from S Section Line, 1415 feet from W Section Line
Lease Name: DENTON A Well #: 1
County: CLARK Total Vertical Depth: 6686 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		6570		WITH 5 SX CMT
CIBP		6658		
COND	20	60		
PROD	5.5	6681	2800	WITH 185 SX CMT
SURF	8.625	728		WITH 375 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/09/2015 4:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SET CIBP @ 6575' OR SAND BACK PERFS WITH 5 SX CMT. PLUG AT 1260' WITH 50 SX CMT. PLUG AT 775' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: NONE
Date/Time Plugging Completed: 06/09/2015 8:00 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

SET CIBP @ 6570' WITH 5 SX CMT. 1ST PLUG AT 1305' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 752' WITH 50 SX CMT. 3RD PLUG AT 310' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
6677	6685		
6663	6666		
6643	6648		
6628	6634		

6/24/15 CKM

KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: CSG

JUN 19 2015
RECEIVED

District: 01

RECEIVED
JUN 16 2015
KCC DODGE CITY

Signed _____
(TECHNICIAN)