

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-025-20751-00-01
Spot: SWNE Sec/Twnshp/Rge: 1-32S-24W
3245 feet from S Section Line, 2035 feet from E Section Line
Lease Name: DENTON RANCH Well #: 1-1 OWWO
County: CLARK Total Vertical Depth: 7400 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		6930		WITH 2 SX CMT
PROD	5.5	6981	2600	WITH 225 SX CMT
SURF	8.625	711		WITH 400 SX CMT

Well Type: SWD UIC Docket No: D28571.0 Date/Time to Plug: 06/05/2015 8:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SET CIBP @ 6930' WITH 2 SX CMT. PLUG AT 1460' WITH 15 SX GEL & 50 SX CMT. PLUG AT 760' WITH 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ROBERT DICKERSON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/05/2015 10:55 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 6930' WITH 2 SX CMT. 1ST PLUG AT 1450' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 748' WITH 50 SX CMT. 3RD PLUG AT 308' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
6981	7400		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: CSG

6/24/15 cem

District: 01

Signed *Eric MacLaren*
(TECHNICIAN)

RECEIVED
JUN - 8 2015
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

JUN 15 2015

CONSERVATION DIVISION
WICHITA, KS

UIC