

1 080219

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,358-00-00

NE NE SE, SEC. 11, T 29 S, R 13 W/W

2310 feet from ~~NE~~ SE Corner of
330 feet from ~~NE~~ SE Corner of

TECHNICIAN'S PLUGGING REPORT

Operator License # 6484

Lease Name Humble Estate Well # 1

Operator: Thornton E. Anderson

County Pratt 155.19

Name & Address 840 1st National Bank Building

Well Total Depth 4775 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 451

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 3:00 pm Day: 20 Month: September Year: 19 84

Plugging proposal received from Bob Brenneman

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" set at 4490' Perfs at 4289-92'

1st plug sand back to 4250' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 150 sx cement

Plugging Proposal Received by J. H. Metz
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:15 pm Day: 20 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2" set at 4490' Perfs at 4289-92'

1st plug sanded back to 4250' and dumped 5 sx cement on top of sand through bailer, 2nd

plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

released 8 5/8" rubber plug and pumped 150 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Maximum pressure 200 psi and shut in pressure 200 psi

OCT 01 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

(If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 10-3-84

Signed J. H. Metz
(TECHNICIAN) SD

INV. NO. 3997