

7-19

1 020245

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,940 - 00-00

SE NE NE, SEC. 8, T 29 S, R. 13 W/K

4290 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Lease Name Barbee Well # 1

Operator: Raymond Oil Company, Inc.

County Pratt 159.32

Name & Address P.O. Box 48788

Well Total Depth 4902 feet

Wichita, KS 67201

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 327

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SHD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Company, Inc. License Number 5929

Address 310 West Central, Suite 117, Wichita, KS 67202

Company to plug at: Hour: 5:30 p.m. Day: 19 Month: 7 Year: 19 89

Plugging proposal received from Gary Pugh

(company name) Duke Drilling Company, Inc. (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 750-780'
1st plug at 780' with 50 sx cement, 2nd plug at 300' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 7:30 p.m. Day: 19 Month: 7 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 780' with 50 sx cement,

2nd plug at 340' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement,

Water well plugged with 5 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by United.

(If additional description is necessary, use BACK of this form.)

(I did not) observe this plugging.

RECEIVED STATE CORPORATION COMMISSION
JUL 31 1989
07-31-89
CONSERVATION DIVISION
Wichita, Kansas

Signed Glenn Barlow (TECHNICIAN)

INVOICED
DATE 8-1-89
INV. NO. 25483

CORRECTED (To correct Lease Name)

FORM MUST BE TYPED
FORM C-1-12/88

State of Kansas
NOTICE OF INTENTION TO DRILL

15- 151-21,940-60-60

CORRECTED COPY
FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date July 15, 1989
month day year

SE NE NE Sec 8 Twp 29 S, R9 13 X West

OPERATOR: License # 5046
Name: Raymond Oil Company, Inc.
Address: P. O. Box 48788
City/State/Zip: Wichita, KS 67201
Contact Person: Pat Raymond
Phone: 316-267-4214

4290 feet from South line of Section
330 feet from East line of Section
(Note: Locate well on Section Plat Below)

CONTRACTOR: License #: 5929
Name: Duke Drilling Co., Inc.

County: Pratt
** Lease Name: Barber Well #: 1
Field Name: Wildcat
Is this a Prorated field? yes X no
Target Formation(s): Lansing, Miss., Viola, Simpson
Nearest lease or unit boundary: 330
Ground Surface Elevation: Estimated 1930 feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water: 200'
Depth to bottom of usable water: 250'
Surface Pipe by Alternate: X 1 300'
Length of Surface Pipe Planned to be set: 300'
Length of Conductor pipe required:
Projected Total Depth: 4875
Formation at Total Depth: Arbuckle
Water Source for Drilling Operations:
X well farm pond other
DWR Permit #: 270' Alt. I Req.
Will Cores Be Taken?: yes X no
If yes, proposed zone:

Well Drilled for: Well Class: Type Equipment:
X Oil ... Inj ... Infield ... Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... CMO ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes

If CMO: old well information as follows:
Operator:
Well Name:
Comp. Dates: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no
If yes, total depth location:

WAS: BARBER

AFFIDAVIT

270' Alt. I Req.

JUL - 7 1989

The undersigned hereby affirms that the drill:

PUSHER Gray Pugh

TD 4902 FORMATION Top sub.

SURFACE PIPE 8 3/4 @ 327'

ANHYDRITE 750' 6050 ELEVATION

STARTING TIME & DATE 5:30 PM 7-19-89

COMPLETION TIME & DATE 7:30 PM 7-19-89

1st PLUG @ 780' FT. W/ 50 SX

2nd PLUG @ 340' FT. W/ 4050 SX

3rd PLUG @ 40 FT. W/ 16 SX

4th PLUG @ FT. W/ SX

RAT HOLE CIRCULATED W/ 15 SX

MOUSE HOLE CIRCULATED W/ 10 SX

WATER WELL PLUGGED W/ 5 SX

CEMENT COMPANY United

TECHNICIAN G.D. D.G.

7-10-89
2578"-300'

~~BARBER~~
G.D. D.G.

RECEIVED
STATE CORPORATION COMMISSION

JUL 31 1989

CONSERVATION DIVISION
Wichita, Kansas

Vertical scale with numbers 5280 to 330

- REMEMBER TO:
- File Drill Pit Application (form EDP-1) with Intent to Drill;
- File Completion Form ACO-1 within 120 days of spud date;
- File acreage attribution plat according to field proration orders;
- Notify appropriate district office 48 hours prior to workover or re-entry;
- Submit plugging report (CP-4) after plugging is completed;
- Obtain written approval before disposing or injecting salt water.