

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-21215-00-00  
Spot: CSWSE Sec/Twnshp/Rge: 35-28S-20W  
660 feet from S Section Line, 1980 feet from E Section Line  
Lease/Unit Name: SHERER B Well Number: 1  
County: KIOWA Total Vertical Depth: 5070 feet

Operator License No.: 5414 Conductor Pipe: Size \_\_\_\_\_ feet:  
Op Name: RICHARDSON, J. MARK/RICHARDSON O Surface Casing: Size 8.625 feet: 620 WITH 400 SX CMT  
Address: 2843 KEYWEST CT. Production: Size 4.5 feet: 5069 WITH 275 SX CMT  
WICHITA, KS 67204 Liner: Size \_\_\_\_\_ feet:

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/02/2001 11:00 AM

Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.

Proposal Rcvd. from: LARRY MITCHELL Company: J. MARK RICHARDSON Phone: (316) 546-3649

Proposed Plugging Method: SAND TO 4600' & 4 SX CMT. 1ST PLUG AT 1250' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 650' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.  
164.78

Plugging Proposal Received By: RICHARD LACEY  
Date/Time Plugging Completed: 04/02/2001 11:30 AM

Witness Type: Plugging Operations 100% Witnessed (Complete)  
KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 4909'. PERFS AT 4684-90'. CIBP @ 4810'. SAND TO 4600' WITH 4 SX CMT ON TOP. ALLIED ON LOCATION. PERFORATE CASING AT 650'. GOT RATE AT 3 BBL PER MINUTE AT 300#. STARTED CMT CIRCULATED 170 SX CMT TO SURFACE & APPROXIMATELY 3 BBL TO PIT.

**INVOICED**  
DATE 4-5-01  
INV. NO. 2001061579

RECEIVED  
STATE CORPORATION COMMISSION

APR - 5 2001  
4-5-01  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed \_\_\_\_\_

(TECHNICIAN)

APR 04 2001

Form CP-273