

To: 1 090165  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,157-00-00 29  
29  
NW NW SW, SEC. 10, T. 28 S, R. 15 W/E  
2310 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3399  
Operator: Farrar Pump & Supply Co., Inc.  
Name & Address P.O. Box 209  
Medicine Lodge, KS 67104

Lease Name Seyfert Well # 1-10  
County Pratt 151<sup>00</sup>  
Well Total Depth 4800 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 406

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635  
Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 9:35 a.m. Day: 11 Month: 2 Year: 19 92

Plugging proposal received from Gary Burke  
(company name) Great Bend Casing Pullers (phone) 316-793-9711

was: 4 1/2" at 4799' w/200 sx cement, Perfs at 4542-46'  
1st plug sand back to 4490' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"  
wiper plug and pump 100 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 13 1992  
02-13-92  
CONSERVATION DIVISION  
Steve Raddleton  
Wichita, Kansas  
(TECHNICIAN)

Plugging Proposal Received by \_\_\_\_\_  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 10:10 a.m. Day: 11 Month: 2 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4490' and dumped 4 sx cement on top of sand  
through bailer,  
2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"  
wiper plug and pump 100 sx cement.  
Maximum pressure 600 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 3384' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I hereby certify that I have observed this plugging.

DATE 2-21-92  
INV. NO. 34618

Signed [Signature]  
(TECHNICIAN)