

15-151-21436-00.00

1-29-88

197

1 040048

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 6/85

C N/2 NW SE, SEC. 8, T 28 S, R 15 W/E

2310 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3399

Lease Name Steve Williams Well # 1

Operator: Farrar Pump & Supply Co., Inc.

County Pratt 158.11

Name & Address P.O. Box 209

Well Total Depth 4865 feet

Medicine Lodge, KS 67104

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 398

Abandoned Oil Well Gas Well Input Well SHD Well O&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address 107 West Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:15 a.m. Day: 29 Month: 1 Year: 19 88

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4694' PBD 4664' Perfs at 4632-40'

1st plug sand back to 4580' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:15 a.m. Day: 29 Month: 1 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back from 4664-4580' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

RECEIVED STATE CORPORATION COMMISSION

Maximum pressure 1000 psi and shut in 750 psi.

FEB 03 1988 2-3-88

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2900' of 5 1/2" casing. (If additional description is necessary, use BACK of this form, Wichita, Kansas)

INVOICED

observe this plugging.

DATE 2-4-88

Signed Stephen J. Pfeifer (TECHNICIAN)

INV. NO. 19717