

To: 1040763 6-18  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API. NUMBER 15-151-21,014-00-00  
SE SE SE, SEC. 6, T 28 S, R 15 WXX  
330 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3399

Lease Name Calbeck Well # 1-6

Operator: Farrar Pump & Supply Co. Inc.

County Pratt

Name & Address P.O. Box 209 Atten: Mike

Well Total Depth 4730 153.72 feet

Medicine Lodge, KS 67104

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 404

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4735

Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 8:30 a.m. Day: 18 Month: 6 Year: 19 93

Plugging proposal received from Mike Farrar

(company name) Farrar Pump & Supply Co. Inc. (phone) 316-886-3763

were: 4 1/2" at 4729' w/200 sx cement, PBSD 4570'. Perfs at 4379-83'

1st plug sand back to 4330' and dump 4 sx cement on top of sand through bailer,

2nd plug pump down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,

100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 9:15 a.m. Day: 18 Month: 6 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4330' and dumped 4 sx cement on top of sand  
bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx  
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement

Maximum pressure 600 psi and shut in 400 psi.

6-23-93 JUN 23 1993

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2570.5' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 2-7-93

Signed Steve Pfeifer  
(TECHNICIAN)

INV. NO. 38045 SEP 15 1993