

To: B 1040996  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-151-21,353-00-00  
NE NE SW, SEC. 6, T 28 S, R 15 W/E  
2310 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 3399  
Operator: Farrar Pump & Supply Co., Inc.  
Name:  
Address P.O. Box 209  
Medicine Lodge, KS 67104

Lease Name Starkey Well # 1-6  
County Pratt 151.48  
Well Total Depth 4661 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 404

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529  
Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 10:15 a.m. Day: 5 Month: 9 Year: 19 95

Plugging proposal received from Richard McIntyre  
(company name) Mike's Testing & Salvage Inc. (phone) 316-938-2943

Work: 4 1/2" at 4653' w/200 sx cement, Open hole 4653-4661'  
1st plug sand back to 4600' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release  
8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 11 a.m. Day: 5 Month: 9 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 4600' and dumped 4 sx cement on top of sand bridge through bailer,  
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.  
Maximum pressure 500 psi and shut in 250 psi.

Remarks: Used 65/35 Pozmix 6% gel by Allied. Recovered 3123' of 4 1/2" casing.

INVOICED  
(Additional description is necessary, use BACK of this form.)  
observe this plugging.

DATE OCT 04 1995  
INV. NO. 43636

Signed Stephen J. Pfeifer  
(TECHNICIAN)

STATE CORPORATION COMMISSION  
WICHITA, KANSAS  
SEP 07 1995  
CONSOLIDATED DIVISION