

1 030329

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,413-00-00
SE SE SW, SEC. 21, T 18²⁸ S, R 15 W/E

330 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6030

Lease Name Baker Well # 1

Operator: Ainsworth Drilling Company

County Pratt 148.85

Name & Address P. O. Box 1269

Well Total Depth 4580 feet

Colorado Springs, CO 80901

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 457

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address P. O. Box 847, Pratt, KS 67124

Company to plug at: Hour: noon Day: 8 Month: November Year: 19 84

Plugging proposal received from Ken Brooks

(company name) Pratt Well Service (phone) 1-800-362-0597

were: Perfs lat: 4576-90'

1st plug sand back to 4525' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 125 sx cement.

Plugging Proposal Received by Steve Overman
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:00 pm Day: 8 Month: November Year: 19 84

ACTUAL PLUGGING REPORT Perfs at 4576-90'

1st plug sanded back to 4525' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

11-21-84 NOV 21 1984

Remarks: Recovered 2500' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by volume.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 12-3-84

Signed Steve Overman
(TECHNICIAN)

INV. NO. 5717 DEC 07 1984