

To: 1 051451
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App. C N/2 SW, SEC. 21, T 28 S, R 15 W
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-25
-API. NUMBER 15-151-21,671-60-00 182R
NW
SEC. 21, T 28 S, R 15 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 5893
Operator: Pratt Well Service, Inc.
Name & Address: P.O. Box 847
Pratt, KS 67124

3630 feet from S section line
4520 feet from E section line
Lease Name Baker Well # 1
County Pratt 160.22
Well Total Depth 4930 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 476

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service, Inc. License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 9:30 a.m. Day: 25 Month: 6 Year: 19 91

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service, Inc. (phone) 316-672-5901

were: 5 1/2" at 4930', Perfs at 4832-4614'
1st plug sand back to 4565' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 25 Month: 6 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4565' and dumped 5 sx cement on top of sand through bailer.

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 500 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2505' of 5 1/2" casing.

INVOICED (If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 7-18-91

Signed Richard W. Lacy (TECHNICIAN)

INV. NO. 32294

RECEIVED
STATE CORPORATION COMMISSION
JUL 19 1991
07-01-91
CONSERVATION DIVISION
Wichita, Kansas