

1 010225

MAR 9 1987

API NUMBER 15-151-21,780-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 50'S
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NE NE, SEC. 20, T 28 S, R 15 W/E

4240 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8709

Lease Name Chubb Well # 1

Operator: White Oilfield Supply, Inc.

County Pratt 159.61

Name & Address 906 South Iowa

Well Total Depth 4911 feet

Pratt, KS 67124

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 403

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11 a.m. Day: 9 Month: 3 Year: 19 87

Plugging proposal received from Dallas Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4908' PBTB 4370' Perfs at 4300-4705' Elevation 2093' GL

1st plug CIBP at 4699 & CIBP at 4370' sand back to 4275' and dump 4 sx cement on top of sand through bailer.

2nd plug pump 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Don Ubel and Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:35 a.m. Day: 9 Month: 3 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4275' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 500 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3800' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (I) observe this plugging.

DATE 3-20-87

INV. NO. 16369

Signed Paul Luthi
(TECHNICIAN) 03-18-87
MAR 18 1987

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
FORM CP-273
Rev. 01-84