

To: 1 120808
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

7-21

API NUMBER 15-151-21,106-00-00
SE SE SE, SEC. 10, T 29 S, R 13 W/E

TECHNICIAN'S PLUGGING REPORT
Operator License # 30323
Operator: P G & E Resources Company
Name
Address 6688 N. Central Expwy., Ste. 1000
Dallas, TX 75206-3922

510 feet from S section line
500 feet from E section line
Lease Name D. Fincham Well # 1
County Pratt
Well Total Depth 4760 #154.70 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 566

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524-0347

Company to plug at: Hour: 9 a.m. Day: 21 Month: 7 Year: 19 93

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4759' w/200 sx cement, PBD 4640', Perfs at 4607-11, 4713-16'

1st plug sand back to 4550' and dump 5 sx cement on top of sand through bailer,
2nd plug pump in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10 a.m. Day: 21 Month: 7 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back 5 1/2" casing to 4550' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.
Maximum pressure 800 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2520' of 5 1/2" casing.

INVOICED (If additional description is necessary, use BACK of this form.)

I (did / ~~XXXXXX~~) observe this plugging.

DATE 7-28-93

INV. NO. 38213

RECEIVED STATE CORPORATION COMMISS

JUL 27 1993

CONSERVATION DIVISION Wichita, Kansas

Signed *Dawn Rusk* (TECHNICIAN)