

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

15-097-2002-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Kiowa SEC. 1 TWP. 28S RGE. 19 XE/W
 Location as in quarters or footage from lines:
C SW NW

Lease Owner Hillenburg Oil Co.
 Lease Name Pyle Well No. 2
 Office Address 11600 South Lynn Lane Broken Arrow, OK. 74011
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry
 Date Well Completed 2-27-84
 Application for plugging filed 2-27-84
 Plugging commenced 2-27-84
 Plugging completed 2-27-84
 Reason for abandonment of well or producing formation _____

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
 Producing formation _____ Depth to top _____ bottom T.D. 4915'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	414'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Spotted 50 sx. cement @ 1190' thru drill pipe.
Spotted 70 sx. cement @ 580' thru drill pipe.
Spotted 10 sx. cement @ 40' thru drill pipe.
Spotted 15 sx. cement in rathole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor White & Ellis Drilling, Inc.
401 E. Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Ernest Sifford (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) [Signature]
401 E. Douglas #500 Wichita
 (Address) Kansas 67202

SUBSCRIBED AND SWORN TO before me this 8th day of March, 19 84


My Commission expires: 

David F. Jamis
 David F. Jamis, Notary Public.

RECEIVED
 STATE CORPORATION COMMISSION

MAR 09 1984 3-9-84

CONSERVATION DIVISION
 Wichita, Kansas



15-097-21002-0000

WHITE

ANDELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: Hillenburg Oil Co. 11600 South Lynn Lane Broken Arrow, OK. 74011

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500, Wichita, Ks. 67202

Lease Name Pyle Well No. 2

Sec. 1 T. 28S R. 19W Spot C SW NW

County Kiowa State Kansas Elevation

Casing Record:

Surface: 8 5/8" @ 414' with 315 SX. 2%gle
3%cc

Production: @ with SX.

Type Well: D & A Total Depth 4915'

Drilling Commenced 2-17-84 Drilling Completed 2-27-84

Formation	From	To	Tops
Cellar	0	7	Anhydrite 1192
Lime, Shale	7	4205	Lansing-Kansas City 4258
Shale, Lime	4205	4258	
Lime	4258	4412	
Shale, Lime	4412	4517	
Lime, Shale	4517	4609	
Shale, Lime	4609	4915	

RECEIVED
STATE CORPORATION COMMISSION

MAR 09 1984

CONSERVATION DIVISION
Wichita, Kansas