

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202  
KANSAS CORPORATION COMMISSION

WELL PLUGGING RECORD  
K.A.R.-82-3-117

09721,351-0000

API NUMBER \_\_\_\_\_

LEASE NAME Mullinville

WELL NUMBER 1

100' Ft. from S Section Line

440' Ft. from E Section Line

SEC. 28 TWP. 285 RGE. 19W (E) or (W)

COUNTY Kiowa

Date Well Completed 3/9/93

Plugging Commenced 3/8/93

Plugging Completed 3/9/93

MAY 13 1993

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

CONSERVATION DIVISION  
LEASE OPERATOR Enron Gas Services, Inc.  
WICHITA, KS

ADDRESS 200 WestLake Park Blvd; Suite 925; Houston TX 77079

PHONE# (713) 531-5686 OPERATORS LICENSE NO. 5278

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3/7/93 (date)

by Steve Durant "Present While Plugging" (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation N/A Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 2376

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Ogalala	Water	0	606'	8 5/8"	X	
Cheyenne	Water	0	606'	8 5/8"	X	
Cedar Hills	Not Present					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set  
175 SX 60:40 POZ W/2% GRL from 2341' to 1473'  
150 SX 60:40 POZ W/2% CALL & 6% GRL from 1211' to 473'  
10 SX 60:40 POZ W/2% CALL & 6% GRL from 40' to 0'


Name of Plugging Contractor Brandt Drilling Company, Inc. License No. 5840

Address 107 N. Market, Ste 914, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Enron Gas Services

STATE OF Kansas COUNTY OF Kiowa, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.



(Signature) Robert G. Mason

(Address) \_\_\_\_\_

before me this 11 day of May, 1993

Patricia A. Pierce  
Notary Public

My Commission Expires: 12-2-96