

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027

WELL PLUGGING RECORD

Wichita, Kansas 67217
NORTH

Kiowa County, Sec 20 Twp 28 Rge (E) 19 (W)

Location as "NE/CNW/SW" or footage from lines C NW NW
Lease Owner Petroleum, Inc.
Lease Name McElwain "B" Well No. 1
Office Address RR #2, Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) gas
Date well completed 19
Application for plugging filed March 20 19 74
Application for plugging approved 19
Plugging commenced March 29 19 74
Plugging completed April 12 19 74
Reason for abandonment of well or producing formation no longer needed



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein

Producing formation Depth to top Bottom Total Depth of Well 4943' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	604'	8 5/8"	604'	none
			4940'	5 1/2"	4940'	4091.15

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sun Cementing pumped in 40 sacks of cement to plug bottom. Set plug at 4600'.
Set 30' rock bridge at 230'. Plugged well with 4 yards of ready mix cement.

RECEIVED
STATE CORPORATION COMMISSION
APR 16 1974
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor PIPE PULLERS, INC.
Address Box 486, Ellinwood, Kansas 67526

STATE OF KANSAS COUNTY OF BARTON
Evelyn Roth (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 15th day of April 1974


My commission expires Feb. 10, 1975
George A. Meyer Notary Public

WELL LOG

15-097-20195-6000

COMPANY Petroleum, Inc.
 FARM McElwain "B" NO. 1
 RID. NO. 3
 TOTAL DEPTH 4943
 COMM. 11-30-73 COMP. 12-13-73
 CONTRACTOR Rains & Williamson Oil Co., Inc.

SEC. 20 T. 28S R. 19W
 LOC. C NW NW



CABING

20	10	5/8" @ 604' w/ 200 sx. 50/50 pos. 2% gel,
15		6 2% cc. & 150 sx. common, 2% cc.
12		
13		5 1/2" @ 4940' w/ 100 sx. 50/50 pos. 10% salt. 10 bbls. salt flush ahead.

FIGURES INDICATE BOTTOM OF FORMATIONS

ELEVATION
 PRODUCTION Oil

Top Hole Soil and Clay	69
Sand	150
Shale	325
Shale, Sand and Shells	760
Shale and Sand	1089
Shale	1140
Shale and Shells	2110
Shale and Lime	2415
Shale and Lime	3255
Lime and Shale	3380
Shale and Lime	3615
Lime	3690
Shale and Lime	3850
Lime	4943
<u>Rotary Total Depth</u>	<u>4943</u>

RECEIVED
 STATE CORPORATION COMMISSION
 APR 17 1974
 CONSERVATION DIVISION
 Wichita, Kansas

State of KANSAS
 County of SEDGWICK ss:

I, Wilson Rains, President of the Rains & Williamson Oil Co., Inc. ~~XXXXXX~~
 upon oath state that the above and foregoing is a true and correct copy of the log of the McElwain "B" #1 well.

Wilson Rains

 WILSON RAINS



Subscribed and sworn to before me this 14th day of December 19 73

Juanita M. Green

 NOTARY PUBLIC
 Juanita M. Green