

15-097-19013-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Kiowa SEC. 14 TWP. 28S RGE. 19 E/W
 Location as in quarters or footage from lines:
2160' from north line & 640' from east line

			x
		14	

Locate Well
 correctly on above
 Section Platt.

Lease Owner TGT Petroleum Corp.
 Lease Name Rice "E" Core Hole No. 1-C
 Office Address 209 E. William, Wichita, Ks. 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): Core Hole
 Date Well Completed 9-3-82
 Application for plugging filed _____
 Plugging commenced 8:00 AM 9-13-82
 Plugging completed 9:20 AM 9-13-82
 Reason for abandonment of well or producing formation Finish logging

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz
 Producing formation _____ Depth to top _____ bottom _____ T.D. 1242
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				5 1/2"	213'	Cemented surface casing

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Halliburton hook-up to 5 1/2" surface casing, mix 2 sacks gel, 2 sacks hulls, pump down on top of 40 visc. mud. Mix & pump in 65 sacks Halliburton common cement (2% gel, 3% cc) 650 lbs. pump in pressure. Clear lines, valve, swedge & landing sub with clear water (3/4 bbl) leaving hole plugged from 10' to 750' - shut in pressure 300#.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor TGT Petroleum Corp.

STATE OF Kansas COUNTY OF Sedgwick, ss.
B. Lynn Herrington (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
 RECEIVED
 STATE CORPORATION COMMISSION (Signature) B. Lynn Herrington
209 E. William-Wichita, Ks
 (Address)

OCT 01 1982

SUBSCRIBED AND SWORN TO before me this 30th day of Sept, 19 82
 Conservation Division
 Wichita, Kansas

My Commission expires: May 17, 1985

Judith K. Moser Notary Public.

