

STATE OF KANSAS
STATE CORPORATION COMMISSION
209 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-297-20327-0000

LEASE NAME Hendershot

WELL NUMBER #1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 13 TWP. 29S RGE. 19W (E) or (W)

COUNTY Kiowa

Date Well Completed 11/22/75

Plugging Commenced 5/11/89

Plugging Completed 5/15/89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Patton Oil Company

ADDRESS 672 W. 4th Street
Hoisington, KS 67544

PHONE# (316) 653-2277 OPERATORS LICENSE NO. 5992

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4860

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	309	none
				5 1/2	4859	3139

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged bottom with sand to 4229', ran 5 sacks cement, shot @3139',
pulled pipe, plugged surface with 400# hulls, 10 sacks gel, 50 sacks
cement, 10 sacks gel, 100# hulls, 8 5/8 plug, 130 sacks 60/40 poz 6% gel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Patton Oil Company

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
statements, and matters herein contained and the log of the above-described well as filed that
the same are true and correct, so help me God.


(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 23rd day of May, 19 89

Notary Public

My Commission Expires:



WELL LOG

JAN 3 1976 REC'D
15-097-20327-0000

COMPANY Patton Oil Company

SEC. 13 T. 28S R. 19W

FARM Hendershot

NO. 1

LOC. C SW/4

TOTAL DEPTH 4850'


COUNTY Kiowa

COMM. 12-22-75

COMP. 1-7-76

CONTRACTOR DaMac Drilling Company, Inc.

CASING 8 5/8 set @ 309



ELEVATION

PRODUCTION

RECEIVED
STATE CORPORATION COMMISSION

JAN 17 1976

CONSERVATION DIVISION
Wichita, Kansas

FIGURES INDICATE BOTTOM OF FORMATIONS

0	175	Clay & Sand
175	525	Shale & Red Bed
525	1535	Shale
1535	3774	Shale & Lime
3774	3876	Lime
3876	4122	Lime & Shale
4122	4291	Lime
4291	4420	Lime & Shale
4420	4850	Lime
4850	4850	RTD

State of Kansas
County of Barton

I, Martha J. McKown of DaMac Drilling Company, Inc.

upon oath state the above and foregoing is a true and correct copy of the log of the Hendershot well.



DONALD SLOUP
STATE NOTARY PUBLIC
Barton County, Kansas
My Commission Expires
November 11, 1978

Martha J. McKown

Subscribed and sworn to before me this 21st day of January 19 76

My Commission Expires: 11-11-73

Donald Sloup
NOTARY PUBLIC