

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

15-097-20676-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Kiowa SEC. 12 TWP. 28S RGE. 19W E/W  
Location as in quarters or footage from lines:

C of NE SW

|  |  |  |  |
|--|--|--|--|
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |

Locate Well  
correctly on above  
Section Platt.

Lease Owner TGT Petroleum Corporation  
Lease Name Baucum Well No. #1  
Office Address 209 E. William Street Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 9-16-81  
Plugging completed 9-21-81  
Reason for abandonment of well or producing formation \_\_\_\_\_

Depleted

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4455'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

| Formation | Content | From | To | Size   | Put in | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8-5/8" | 640'   | none       |
|           |         |      |    | 5-1/2" | 4452'  | 3493'      |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

~~Moved in on location, made bottom plug back with sand to 4250' and set 5 sacks cement.  
Pulled 30" tension, shot pipe @3735', 3615' and 3490. Pulled a total of 82 joints  
of pipe. Plugged well with 4 sacks hulls, 10 sacks gel, 8-5/8" plug, 50 sacks cement,  
7 sacks gel, 35 sacks cement, 8 sacks gel, and 15 sacks cement. Plugging Complete.~~

RECEIVED  
STATE CORPORATION COMMISSION  
9-24-81  
SEP 24 1981

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling CONSERVATION DIVISION  
Wichita, Kansas


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
R. Darrell Kelso  
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of September, 19 81

My Commission expires:



Irene Hoover  
Notary Public.

CONTRACTOR'S WELL LOG

REC-1  
JAN 23 1981

5-097-20676-0000

|                  |   |
|------------------|---|
| OPERATOR:        | TGT Petroleum Corporation                         |
| CONTRACTOR:      | Abercrombie Drilling, Inc.                        |
| WELL NAME:       | BAUCUM #1   |
| LOCATION:        | SE SW, Section 12-28S-19W<br>Kiowa County, Kansas |
| SPUD DATE:       | 12/31/80  |
| COMPLETION DATE: | 1/17/81   |

|     |      |                    |
|-----|------|--------------------|
| 0   | 645  | Redbed & Shale     |
| 645 | 5100 | Lime & Shale       |
|     | 5100 | Rotary Total Depth |

Spud @ 6:45 p.m., 12/31/80. Drilled 645' in a 12 1/4" hole. Ran 15 jts. of 8 5/8" - 24# casing (tally 630.38 overall) Set @ 640'. Cemented with 250 sx. of Halco Lite, 2% gel, 3% c.c. Followed with 100 sx. of common 3% c.c., 1/4# Flocel per sack. Cement did circulate. Job was complete @ 7:00 a.m., 12/31/80. Waiting on cement.

T.D. @ 5100'. Ran 106 jts. of 5 1/2" - 14# casing (tally 4458.08) Set @ 4452', Cemented with 50 sx. of Halliburton Lite, 12 1/2# gilsinite per sack, 6% gel followed with 100 sx. of 50-50 posmix, 10% salt saturated. Job was completed @ 11:00 p.m., 1/17/81.

SAMPLE TOPS:

Anhydrite 1178'  
B/Anhydrite 1212'

STATE OF KANSAS )  
 ) SS  
COUNTY OF SEDGWICK )

Jack L. Partridge, Assistant Secretary/Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the BAUCUM #1, SE SW, Section 12-28S-19W, Kiowa County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge  
Jack L. Partridge, Asst. Sec./Treas

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 20th day of January, 1981.

Jeanette A. Metheny  
Jeanette A. Metheny, Notary Public

