

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-097-20,893-6000

LEASE NAME Pyle-Taylor A

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 2

990 Ft. from S Section Line

1660 Ft. from E Section Line

SEC. 12 TWP. 28 SRGE. 19 (W)

COUNTY Kiowa

LEASE OPERATOR TGT Petroleum Corp.

ADDRESS 7570 W. 21st-Bldg 1010-D, Wichita, Ks.

PHONE# (316) 773-2266 OPERATORS LICENSE NO. 5118

Date Well Completed 3-28-83

Character of Well Gas

Plugging Commenced 12/1/00

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12/4/00

The plugging proposal was approved on _____ (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filed? Yes . If not, is well log attached? _____

Producing Formation Mississippi Depth to Top _____ Bottom _____ T.D. 5002

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	524'	-0-
				4 1/2	4999'	2993.70

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Plug back to 4600'/w/sand. Dump four sacks on sand plug. Pull to 1180'. Pumped ten sacks gel and 50 sack plug. Pull to 550'; pump 50 sacks and pull pipe. Circulate cement from 40' to surface. All cement 60/40 Posmix/w/6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor TGT Petroleum Corp. License No. 5118

Address 7570 W. 21st-Bldg. 1010-D, Wichita, Ks. 67205

RECEIVED
KANSAS CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: TGT Petroleum Corp.

STATE OF Kansas COUNTY OF Sedgwick, ss.

JAN 08 2001


B. Lynn Herrington (Employee of Operator Conservation Division) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) B. Lynn Herrington

(Address) 7570 W. 21st-Bldg. 1010-D

Wichita, Ks. 67205

WITNESSED AND SWORN TO before me this 3rd day of January, 2001



Judith K. Moser Notary Public

My Commission Expires: May 17, 2001