

15-097-20928-0000

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Kiowa SEC. 10 TWP. 28S RGE. 19  W  
 Location as in quarters or footage from lines:  
 N.E. N.E. N.W.


Locate Well  
 correctly on above  
 Section Platt.

Lease Owner Cinco Exploration  
 Lease Name Lee Lucas Well No. 1  
 Office Address Box 3723/Victoria, TX/77903  
 Character of Well (Completed as Oil, Gas or Dry Hole): gas  
 Date Well Completed 12/82 A.P.I. 15-097-20928  
 Application for plugging filed 04/83  
 Plugging commenced 05/04/83  
 Plugging completed 05/10/83  
 Reason for abandonment of well or producing formation dry

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Tarbutton/Durant  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4948  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	454	none
				4 1/2	4947	3250

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set. Set Bridge plug at 4210  
4 sacks of cement to 4258  
3 hull, 10 jell, 50 cement, 10 jell, 1 hull, plug, 120 cement  
60-40 P.O.Z. 2% jell, 3% c.c.  
Zimmerman on location

(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor Clarke Corp.

STATE OF Kansas COUNTY OF Barber, ss.  
Edmo. J. Morgenstern (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) Edmo. J. Morgenstern  
Medicine Lodge, Mo.  
 (Address)

SUBSCRIBED AND SWORN TO before me this 27th day of May, 1983  
Jessie Hamilton  
 Notary Public.

My Commission expires: April 4, 1984.

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAY 31 1983 5-31-83  
 CONSERVATION DIVISION  
 Wichita, Kansas

15-097-20928-0000

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Kiowa SEC. 10 TWP. 28S RGE. 19 N W  
 Location as in quarters or footage from lines:

NE, NE, NW 330' FNL & 2310' FWL of Section


Lease Owner CINCO EXPLORATION COMPANY ET AL

Lease Name Lee E. Lucas Well No. 1

Office Address P. O. Box 3723 - Victoria, Texas 77903

Character of Well (Completed as Oil, Gas or Dry Hole) Oil

Date Well Completed 02/23/83

Application for plugging filed 04/21/83

Plugging commenced 05/04/83

Plugging completed 05/09/83

Reason for abandonment of well or producing formation

Non-Commercial

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant

Producing formation Kansas City & Cherokee Depth to top 4258' bottom 4798' T.D. 4970'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put In	Pulled Out
Fresh Water Sands	Fresh Water	0	400			
Kansas City	Oil	4249	4603			
Cherokee	Oil & Gas	4774	4828	8 5/8	454	0
				4 1/2	4947	3240

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set. Pumped the following in sequence: 3 sacks hulls, from 820' to 850', 10 sacks gel from 775' to 820', 50 sacks cement from 550' to 775', 10 sacks gel from 510' to 550', 1 sack hulls from 500' to 510' and 120 sacks cement from 0' to 500'.

Bridge plug @ 4210'  
Dumped cement to 4180'

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton - Pratt, Kansas, Clarke Corporation - Medicine Lodge, Kansas

STATE OF TEXAS COUNTY OF VICTORIA, ss.

MELVIN KLOTZMAN

(employee of owner) or ~~(owner)~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

MAY 19 1983 (Signature) [Signature]

CONSERVATION DIVISION  
 Wichita, Kansas

P. O. Box 3723 - Victoria, TX 77903  
 (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of May, 1983

Doris Davenport

My Commission Expires: 12-07-84

DORIS DAVENPORT  
 Notary Public, Victoria County, Texas