

15-097-30003-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 22 1965

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Calvert-Mid-American, Inc.

Complete Address: Box 911, Cushing, Oklahoma

Lease Name Schwarm Well No. # 1

Location NE SW Sec. 32 Twp. 29 Rge. 17 (E) (W) W

County Kiowa Total Depth 4884'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 3:30 PM Day 20th Month Nov. Year 1965

The Above well was plugged as follows:

435' of 8 5/8" surface pipe, cement circulated. 4884' of 4 1/2" long string,
cemented with the temperature survey ay 4375'. Plug back to 4880'. Top
perferation 4879'. Bottom of the hole was sanded to 4870', and cemented
with 3 sacks. 4250' of 4 1/2" long string was recovered from the hole.
Fluid in the hole was bailed down to 300', bridge plug and rock bridge
from 300' to 290', and cemented with 25 sacks. Hole was filled with mud to
40', bridge of rock from 40' to 30', and cemented with 10 sacks to the
base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 11-22-65

INV. NO. 2227-W