

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
CONSERVATION DIVISION
WICHITA, KANSASJ. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, KansasWell Plugging Authority,
issued January 5, 1967

JAN 31 1967

1-31-67
CONSERVATION DIVISION
WICHITA, KANSASOperator's Full Name Jas. F. SmithComplete Address: Box 10005, Amarillo, TexasLease Name Conklin Well No. # 1Location SW SW SW Sec. 11 Twp. 29 Rge. 17 (E) (W)County Kiowa Total Depth 5125'Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Daco Well Servicing CompanyAddress: 1700 South Main, Borger, Texas License No. 138Operation Completed: Hour 1:30PM Day 30th Month Jan. Year 1967

The Above well was plugged as follows:

152' of 13 3/8" surface pipe, cement circulated. 5124' of 4 1/2" long string, with the top of the cement at 3930'. Cast iron plug set at 4960'. Top perforation 4694'. 25 sacks of cement was pumped on bottom to a pressure of 600 lbs, bringing the top of the cement to 4520'. 2530' of 4 1/2" long string was recovered from the hole. 8 sacks of Gel-Mud and 70 sacks of cement with 2% Gel-Mud was pumped through the 4 1/2" at 225', and let set over-night. Next day the top of the cement was tagged below the surface pipe, at 229'. 50 sacks of cement with 2% Gel-Mud was pumped through the 4 1/2" at 164'. 3 hours later the top of the cement was tagged at 120' in the surface pipe. Hole was capped with 25 sacks of cement from 28' to the base of the cellar. Daco Well Service pumped the cement.
 I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging SupervisorDATE 1/31/67INV. NO. 4690-W