

15-097-30092-0000

Form CP-3  
Rev. 6-26-62KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, KansasRECEIVED  
STATE CORPORATION COMMISSION

SEP 7 1965

CONSERVATION DIVISION  
Wichita, KansasOperator's Full Name Union Oil of CaliforniaComplete Address: 619 West Texas Ave., Midland, TexasLease Name Robbins Well No. # 1-25Location APP C NW SE  
1980' FSL & 1880' FEL Sec. 25 Twp. 29 Rge. 17 (E) (W) WCounty Kiowa Total Depth 4710'Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A        X       Other well as hereafter indicated:       Plugging Contractor: Strata Drilling, Inc.Address: 2421 Tenth St., Great Bend, Kansas License No.       Operation Completed: Hour 1:00 PM Day 5th Month Sept. Year 1965

The Above well was plugged as follows:

602' of 8 5/8" surface pipe, cement circulated with 400 sacks. 30 sacks  
of cement was spotted on bottom at 4710'. Hole was filled with drilling  
mud to 300', 1st cementing plug, bridged solid with hulls, and cemented  
with 25 sacks. Hole was filled with drilling mud to 40', 2nd cementing  
plug, bridged solid with hulls on fluid at 40', and cemented with 10  
sacks to the base of the cellar. Rat and mouse holes bridged and cemented  
with 5 sacks.

This cementing was done by Dowell Chemical Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving  
Well Plugging SupervisorDATE 9/8/65  
INV. NO. 1968-W