

1041350

TO: STATE CORPORATION COMMISSION

510

API NUMBER 15-097-20,279-0600  
NW NW SEC. 36, T 28 S, R 19 W

CONSERVATION DIVISION - PLUGGING SECTION 4470 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4620 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME JOY STATION WELL # E-3

TECHNICIAN'S PLUGGING REPORT

COUNTY KIOWA 161.10

OPERATOR LICENSE # 5123

WELL TOTAL DEPTH 4957 FEET

OPERATOR: PICKRELL DRILLING COMPANY, INC PRODUCTION CSG: SIZE 4 1/2" @ 4849' WITH 150 SX

NAME AND 110 N MARKET, SUITE 205 SURFACE CASING: SIZE 8 5/8" @ 258' WITH 180 SX

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL E-25,689 D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR CLARK CORPORATION LICENSE NUMBER 5105

ADDRESS PO BOX 187 MEDICINE LODGE, KS 67104

COMPANY TO PLUG AT: HOUR: 1:00 PM DAY: 10 MONTH: 05 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM ALAN VRATIL

(COMPANY NAME) CLARK CORPORATION (PHONE) 316-886-5665

WERE: PERFS AT 4702-4706

SANDED BACK TO 4600' AND PUT 4 SX CEMENT ON TOP OF SAND BRIDGE WITH BAILER.

PUMPED DOWN 8 5/8" SURFACE PIPE WITH 300# HULLS, 10 SX GEL, 50 SX CEMENT, 10 SX GEL, 100#

HULLS, 150 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 1:45 PM DAY: 10 MONTH: 05 YEAR: 1999

ACTUAL PLUGGING REPORT

SANDED BACK TO 4600' AND PUT 4 SX PORTLAND CEMENT ON TOP OF SAND BRIDGE WITH BAILER.

PUMPED DOWN 8 5/8" SURFACE PIPE WITH 300# HULLS, 10 SX GEL, 50 SX CEMENT, 10 SX GEL,

100# HULLS, 150 SX CEMENT. MAXIMUM PSI @ 600#. SHUT IN WITH 25#.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2600' OF 4 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

INVOICED STATE CORPORATION COMMISSION  
I (IND) OBSERVE THIS PLUGGING.

SIGNED Stephen J. Pfeifer  
(TECHNICIAN) FORM CP-2/3

DATE 5-21-99

MAY 19 1999

INV. NO. 60967

CONSERVATION DIVISION  
Wichita, Kansas

5-19-99