

1041401

TO: STATE CORPORATION COMMISSION

API NUMBER 15-097-00218 -6000
NW NW SEC. 1, T 28 S, R 19 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4620 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME PYLE WELL # 1
COUNTY KIOWA 157.72

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5375 WELL TOTAL DEPTH 4853 FEET

OPERATOR: HILLENBURG OIL COMPANY PRODUCTION CSG: SIZE 4 1/2" @ 4852' WITH 100 SX

NAME AND 11600 S LYNN LANE RD. SURFACE CASING: SIZE 8 5/8" @ 344' WITH 300 SX

ADDRESS BROKEN ARROW, OK 74011

ABANDONED OIL WELL GAS WELL INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 12:30 PM DAY: 23 MONTH: 06 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM MONTE ANDREWS

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: TOP PERF 4823-33

SAND BACK TO 4750' & 4 SX CEMENT. 1ST PLUG AT 1200' WITH 50 SX CEMENT. 2ND PLUG AT 370' WITH 50 SX CEMENT. 3RD PLUG AT 0-40' WITH 10 SX CEMENT.

STATE CORPORATION COMMISSION

7-14-00 JUL 14 2000

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING PROPOSAL RECEIVED BY SCOTT ALBERG

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 2:00 PM DAY: 23 MONTH: 06 YEAR: 2000

ACTUAL PLUGGING REPORT

SAND BACK TO 4650' AND PUT 4 SX CEMENT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER.

LOAD HOLE WITH GEL. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 1200' WITH 50 SX CEMENT.

2ND PLUG AT 370' WITH 50 SX CEMENT. 3RD PLUG AT 40' WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2800' OF 4 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

DATE 7/18/00 SIGNED Stephen J. Resler (TECHNICIAN) FORM/CP-2/3

WV. NO. 1062080

6/23

INVOICE