

1 060186

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097-21,002-0000

NW 1, SEC. 1, T 28 S, R 19 ~~W~~

1980 feet from N ~~W~~ section line

660 feet from W ~~E~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5375

Lease Name Pyle Well # 2

Operator: Hillenburg Oil Company

County Kiowa

Name & Address 11600 Lynn Lane Road

Well Total Depth 4915 159.73 feet

Broken Arrow, OK 74011

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 414

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor White & Ellis Drilling, Inc. License Number 5420

Address 401 East Douglas - #500, Wichita, KS 67202

Company to plug at: Hour: 10:00 pm Day: 27 Month: February Year: 19 84

Plugging proposal received from Judy Steiben

(company name) White & Ellis (phone) 316-792-2424

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 1190' with 50 sx cement

2nd plug at 580' with 70 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 11:00 pm Day: 27 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1190' with 50 sx cement, 2nd plug at 580' with
70 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface
with 10 sx cement, 5th plug to circulate rathole with 15 sx cement

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Allied Ticket No. 41992
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-8-84

INV. NO. 0594

RECEIVED
STATE CORPORATION COMMISSION

MAR 07 1984

Paul A. Luthi
(TECHNICIAN)

3-7-84

CONSERVATION DIVISION
Wichita, Kan.

FORM CP-2/3
Rev. 01-84