

To: 1 040878
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

8-9

API NUMBER 15- 097-21,272-000 Docket #E-25,689

SE NW SE, SEC. 35, T 28 S, R 19 W
1650 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5123

Lease Name Joy Station Unit Well # T-2

Operator: Pickrell Drilling Company, Inc.
Name &
Address 110 N. Market, Ste. 205
Wichita, KS 67202

County Kiowa
Well Total Depth 4800 156.00 feet

Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 270

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 3:30 p.m. Day: 9 Month: 8 Year: 19 94

Plugging proposal received from Richard McIntyre
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

Work: 4 1/2" at 4790' w/150 sx cement, PBTD 4755', Perfs at 4714-18'
1st plug sand back to 4616' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper
plug and pump 150 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 9 Month: 8 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 4616' and dumped 4 sx cement on top of sand
bridge through bailer,
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 600 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2632' of 4 1/2" casing
(If additional description is necessary, use BACK of this form.)
observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION
AUG 17 1994

INVOICED

DATE 8-26-94
WV. NO. 41029

Signed Stephen J. Pfeiffer
(TECHNICIAN)