

To: 1 120506
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-21,103 -0000

SWNESE, SEC. 27, T 28 S, R 19 WE

1650 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7368

Lease Name Cossell Well # 1-27

Operator: Pacific Enterprises Oil Co

County Kiowa 162.50

Name & Address Box 76499

Well Total Depth 5000 feet

OKla City, OKla

Conductor Pipe: Size _____ feet

73147-2944

Surface Casing: Size 8 5/8 feet 434

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 176 Chase Ks 67524

Company to plug at: Hour: 10³⁰ AM Day: 13 Month: 12 Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

work: Sand 4 1/2" casing back to 4444' & 45x cement @ dump boiler
Pump in 8 5/8" surface casing @ 300# hulls, 10sx gel, 50sx cement,
10sx gel, 100# hulls, 8 5/8" wiper plug & 150sx cement.

Recovered: 2827' of 4 1/2" casing

4 1/2" casing set @ 4999' cemented @ 250sx cement PBTD @ 4949' Perf @
4494-4909 (3 sets)

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11³⁰ AM Day: 13 Month: 12 Year: 19 90

ACTUAL PLUGGING REPORT Sanded 4 1/2" casing back to 4444' & 45x cement @ boiler
Pumped into 8 5/8" surface casing @ 300# hulls, 10sx gel,
50sx cement, 10sx gel, 100# hulls & 150sx cement.

Pumping pressure 0 - 200 # Shut in pressure 200 #

Remarks: Cemented by Howco- 60-46-670 gel
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 09 1991

INV. NO. 30448

DEC 16 1990

12-16-90
CONSERVATION DIVISION
Wichita, Kansas

Signed Duan Rankin
(TECHNICIAN)