

5-15

15-097-20327-0000

1 080043

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 12/22/75

C SW/4, SEC. 13, T 28 S, R 19 W/E

1320 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5992

Lease Name Hendershot Well # 1

Operator: Patton Oil Company

County Kiowa 157.95

Name & Address 672 West 4th Street

Well Total Depth 4860 feet

Hoisington, KS 67544

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 309

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2:25 p.m. Day: 15 Month: 5 Year: 1989

Plugging proposal received from Bill Reed

(company name) Patton Oil Company (phone) 316-653-2277

were: 5 1/2" at 4859' PBD 4540' Perfs at 4273-79'

1st plug sand back to 4230' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 130 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
5-17-89

MAY 17 1989

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Conservation Division  
Wichita, Kansas

Operations Completed: Hour: 3:20 p.m. Day: 15 Month: 5 Year: 1989

ACTUAL PLUGGING REPORT 1st plug sanded back to 4230' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 8 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 2 sx hulls, released 8 5/8" wiper plug and pumped 130 sx cement.

Maximum pressure 900 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3200' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

DATE 5-22-89

Signed Mike Spain  
(TECHNICIAN)

INV. NO. 24898