

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-20920-00-00
Spot: CSESW Sec/Twnshp/Rge: 3-28S-19W
600 feet from S Section Line, 1980 feet from W Section Line
Lease/Unit Name: MILLER_B Well Number: 1
County: KIOWA Total Vertical Depth: 4945 feet

Operator License No.: 5118 Conductor Pipe: Size _____ feet:
Op Name: TGT PETROLEUM CORPORATION Surface Casing: Size 8.625 feet: 455 WITH 355 SX CMT
Address: 7570 W 21ST ST N, STE1010D PO BOX 75 Production: Size 4.5 feet: 4944 WITH 225 SX CMT
WICHITA, KS 67275 Liner: Size _____ feet:

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/08/2001 11:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: HAROLD BELLERIVE Company: TGT PETROLEUM CORP Phone: (316) 773-2266

Proposed Plugging Method: SAND TO 4750' & 4 SX CMT. 1ST PLUG AT 1262' WITH 50 SX CMT. 2ND PLUG AT 485' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 15 SX CMT.
160071

Plugging Proposal Received By: STEVE MIDDLETON

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 03/08/2001 12:45 PM

KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4920'. PERFS AT 4806-13' & 4870-75'. SET CIBP @ 4000' & PUT 2 SX CMT ON TOP OF CIBP. SPOT PLUGS THROUGH 4 1/2" CASING. LOAD HOLE WITH GEL. 1ST PLUG AT 1250' WITH 50 SX CMT. 2ND PLUG AT 485' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

INVOICED

DATE 3-30-01

INV. NO: 2001061562

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 3010' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
Form CP-200

MAR 12 2001

MAR 22 2001

3-22-01

CONSERVATION DIVISION