

To: 1 030836
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C W/2 SE NE, SEC. 2, T 28 S, R 19 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

7-22-87
API NUMBER 15- 097-20,892-000
3200 feet from S section line
1040 feet from E section line
Farms

TECHNICIAN'S PLUGGING REPORT

Operator License # 5118
Operator: TGT Petroleum Corporation
Name &
Address 209 East William
Wichita, KS 67202

Lease Name Pyle-Taylor Well # 2
County Kiowa 160.94
Well Total Depth 4952 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 519

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 8 a.m. Day: 22 Month: 7 Year: 19 87

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 4951' PBD 4929' Perfs at 4825-30, 4813-19' Elevation 2283'GL

1st plug sand back to 4760' and dump 5 sx cement on top of sand through bailer,

2nd plug at 1239' with 40 sx cement, 3rd plug at 540' with 40 sx cement,

4th plug at 40' with 20 sx cement down 8 5/8".

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 22 Month: 7 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sand back to 4760' with 5 sx cement on top of sand through bailer,

2nd plug at 1227' with 40 sx cement, pulled 5 joints tubing, pumped 55 barrels mud,

3rd plug at 540' with 40 sx cement, pulled 5 joints tubing, pumped 15 barrels mud,

waited on cement to set for 2 hours,

4th plug squeezed 8 5/8" with 40 sx cement from surface. Hole in casing at 80'.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2400' of 5 1/2" casing
(If additional description is necessary, use BACK of this form.)

INVOICED
observe this plugging.

Signed Steve Dumont
(TECHNICIAN)

RECEIVED
7-24-87
JUL 24 1987

DATE 7-24-87
INV. NO. 17626 7-22