

1050301

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 097-21,047-0000

C SE NW, SEC. 2, T 27 S, R 19 (W) E  
3490 feet from N SE Corner of  
3090 feet from W SE Corner of

TECHNICIAN'S PLUGGING REPORT

Operator License # 5118

Lease Name Nan Well # 2(twin)

Operator: TGT Petroleum Corporation

County Kiowa

Name & Address 209 East William

Well Total Depth 5020 163.15 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 525

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 7:30 am Day: 4 Month: August Year: 19 84

Plugging proposal received from Harvey Moore, Jr.

(company name) Abercrombie (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1230' with 50 sx cement

2nd plug at 600' with 50 sx cement  
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement. Plug water well with 5 sx cement

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:00 am Day: 4 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1230' with 50 sx cement, 2nd plug at 600' with 50 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate mouse hole with 10 sx cement. Plugged water well with 5 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton  
(If additional description is necessary, use BACK of this form)

(XXX) did not observe this plugging.

RECEIVED STATE CORPORATION COMMISSION  
AUG 07 1984  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED  
DATE 8-17-84  
INV. NO. 3234

Signed Richard W. Lacey (TECHNICIAN)

8-16 SEP 11 1984