

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-057- 20 317-0000

NW, Sec. 35, T 29 S, R 24 W/E

2310 feet from N/S section line

2310 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6029

Lease Name Peterson Well # 2

Operator: Ladd Petroleum And PL&E.
Name & Address: Box 2848
Tulsa Oklahoma 74101

County Ford

Well Total Depth 5500 feet \$178.75

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1400

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor H-30 Drilling Inc License Number 5107

Address 251 N. Water, Wichita Kansas 67202

Company to plug at: Hour: 10:00 PM Day: 21 Month: April Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO E. J. Woody

(company name) (phone)

were: To use 50/50 Poz mix, 4% Gel - 3% CC & spot 1st plug @ 1440 ft / 50 SX cement; 2nd Plug @ 720 ft / 40 SX cement; 3rd plug @ 40' with Solid Bridge of Halls and 8 5/8 Rubber plug; 4th plug @ 40-0' with 10 SX cement, 15 SX cement circulated in Rat hole, 10 SX cement in mouse hole; circ 5 SX in water well.

Orders by R. Thornton

Signed Benny E Beck (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:00 AM Day: 22 Month: April Year: 19 83

ACTUAL PLUGGING REPORT Plugged as ordered.

Hall, Burton did the cementing.

RECEIVED STATE CORPORATION COMMISSION

APR 26 1983

CONSERVATION DIVISION Wichita, Kansas

Remarks: Elev. 2580' @ GL

anhydrite top @ 1400'

I hereby certify that the above plugging instructions were given as herein stated and that I (did/did not) observe this plugging.

Signed Benny E Beck KPHC (TECHNICIAN)

FORM CP-2/3 Rev. 9-82

INVOICED

DATE 5-4-83

INV. NO. 4160-W