

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION NW NW NW , Sec. 33 , T 29 S, R 24 W/K  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 057- 20,360 - 0000

330 feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

330 feet from W/E section line

Operator License # 6029

Lease Name Shelor Well # 2-33

Operator: Ladd Petroleum Corp.  
Name & P. O. Box 2848  
Address Tulsa, OK 74101

County Ford

Well Total Depth 5435 feet 176.63

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1439

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Rains & Williamson Oil Co., Inc. License Number 5146

Address 435 Page Court, 200 W. Douglas, Wichita, KS 67202

Company to plug at: Hour: 1:00 am Day: 28 Month: January Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Mike Godfrey

(company name) Raines & Williamson (phone) 316-265-9686

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 1420' with 50 sx cement

2nd plug at 640' with 50 s x cement  
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 15 sx cement

6th plug to circulate mousehole with 10 sx cement.

Signed Paul A. Luthie  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:00 am Day: 28 Month: January Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1420' with 50 sx cement, 2nd plug at 640' with

50 sx cement, 3rd & 4th plugs solid bridge - hulls - plug at 40' -- cement to

surface with 10 sx cement. 5th & 6th plugs to circulate rathole and mousehole -

rathole with 15 sx cement and mouse hole with 10 sx cement.

Remarks: Use 60/40 Pozmix, 2% gel, 3% cc. by Halliburton

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 02 1984  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed Paul A. Luthie  
(TECHNICIAN)

INVOICED

DATE 2-3-84  
DATE  
INV. NO. 0045