

To: 1 090754
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-057-20,396-0000
SW SW SW, SEC. 32, T 29 S, R 24 W/E
330 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License / 5123
Operator: Pickrell Drilling Company, Inc.
Name
Address 110 N. Market, Ste. 205
Wichita, KS 67202

Lease Name Moore "U" Well # 3
County Ford 177.80
Well Total Depth 5471 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 520

Abandoned Oil Well Gas Well Input Well SMD Well O&A
Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 10:45 a.m. Day: 4 Month: 11 Year: 19 96

Plugging proposal received from James
(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

Work: 4 1/2" at 5460' w/150 sx cement, PBTD 5422', Perfs at 5286-89'

1st plug sand back to 5225' and dump .5 sx cement on top of sand through bailer,

2nd plug at 1510' with 50 sx cement,

3rd plug at 550' with 50 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Bill Johnson (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:40 a.m. Day: 4 Month: 11 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 5225' and dumped 4 sx cement on top of sand through bailer,

2nd plug spotted through casing at 1510' with 10 sx gel and 50 sx cement,

3rd plug pulled to 550' and spotted 5 sx gel and 50 sx cement,

4th plug pulled to 40' and circulated cement to surface.


Remarks: Used 60/40 6% gel by Allied. Recovered 2618' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

1 (and/or ~~more~~) observe this plugging.

INVOICED

DATE NOV 13 1996

INV. NO. 46954

Signed  (TECHNICIAN)