

To: 1051860
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

11-3

API NUMBER 15-057-20,326-0000

S/2 SE SW, SEC. 32, T 29 S, R 24 W/E
330 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5123
Operator: Pickrell Drilling Company, Inc.
Name & Address 110 N. Market, Ste. 205
Wichita, KS 67202

Lease Name Moore U Well # 1
County Ford
Well Total Depth 5398 175.44 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 531

Abandoned Oil Well Gas Well X Input Well SWD Well O&A
Other well as hereinafter indicated

Plugging Contractor Peters Drilling Co., Inc. License Number 3400
Address P.O. Box 742, Great Bend, KS 67530-0742

Company to plug at: Hour: 8:30 a.m. Day: 3 Month: 11 Year: 1994

Plugging proposal received from Mike Peters
(company name) Peters Drilling Co. (phone) 316-793-6721

were: 4 1/2" at 5374' w/150 sx cement, PBSD 5326', Perfs at 5276-82'
1st plug sand back to 5220' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 150 sx cement.

 Plugging Proposal Received by Steve Pfeifer
 (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 9:40 a.m. Day: 3 Month: 11 Year: 1994

ACTUAL PLUGGING REPORT 1st plug sanded back to 5220' and dumped 4 sx cement on top of sand
through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls; released
8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 500 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2750' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 11-30-94 12-1-94

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 41772
11-3 JAN 19 1995