

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-057-20340-00-00  
Spot: CSESENE Sec/Twnshp/Rge: 32-29S-24W  
2310 feet from N Section Line, 330 feet from E Section Line  
Lease/Unit Name: DUFFORD Well Number: 2-A  
County: FORD Total Vertical Depth: 5450 feet

Operator License No.: 5123 Conductor Pipe: Size \_\_\_\_\_ feet:  
Operator Name: PICKRELL DRILLING COMPANY Surface Casing: Size 8.625 feet: 612 WITH 300 SX CMT  
Address: 100 SOUTH MAIN - SUITE 505 Production: Size 4.5 feet: 5445 WITH 150 SX CMT  
WICHITA, KS 67202 Liner: Size \_\_\_\_\_ feet: 177.13

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/16/2000 11:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: TONY DUMLER Company: PICKRELL DRILLING CO. Phone: (316) 262-8427

Proposed Plugging Method: PUMP 300# HULLS & 25 SX CMT. GEL SPACER TO 1575'. PUMP CMT FROM 1575' TO SURFACE. PUMP 50 SX CMT DOWN 8 5/8 X 4 1/2.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 11/16/2000 11:45 AM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

CASING LEAK AT 602'. SQUEEZED WITH 100 SX CMT TO SURFACE. PUMP DOWN 4 1/2" CASING WITH 25 SX CMT & 3 HULLS. GEL TO 1600'. PUMP 125 SX CMT TO SURFACE. PUMP PRESSURE 700#. SHUT IN PRESSURE 700#. CHECK BACKSIDE. HAD CEMENT IN PIPE AND VALVE. BACKSIDE FULL OF CEMENT FROM 602' TO SURFACE.

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

NOV 27 2000  
11-7-00  
CONSERVATION DIVISION  
Wichita, Kansas

District: 01

Signed \_\_\_\_\_  
(TECHNICIAN)

INVOICED  
DATE 11/28/00 NOV 20 2000  
NOV. 20 2000  
2001061019 MP

[Signature]  
Form CP 2/3