

1060194

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION W/2
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 057-20,372 - 0000
NW SW, SEC. 31, T 29 S, R 24 W/E

1980 feet from ~~W/S~~ section line
330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6033

Lease Name Rooney Well # 1-31
County Ford

Operator: Murfin Drilling Co.
Name & Address 250 N. Water, Suite 300
Wichita, KS 67202

Well Total Depth 5400 175.50 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 660

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Rine Drilling Company License Number 5654

Address 300 W. Douglas, Suite 600, Wichita, KS 67202

Company to plug at: Hour: 7:00 pm Day: 7 Month: March Year: 19 84

Plugging proposal received from Lloyd Hubbard

(company name) Rine Drilling Company (phone) 316-267-1333

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 1530' with 50 sx cement

2nd plug at 1080' with 50 sx cement

3rd plug at 690' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 15 sx cement, 7th plug to circulate mousehole with 10 sx cement. Plug water Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)
well with 5 sx cement

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 8:45 pm Day: 7 Month: March Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1530' with 50 sx cement, 2nd plug at 1080' with

50 sx cement, 3rd plug at 690' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rathole with

15 sx cement, 7th plug to circulate mousehole with 10 sx cement, plug water well with

5 sx cement.

Bob Tarbutton gave the orders and Paul Luthi saw the entire operation

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Halliburton
(if additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED STATE CORPORATION COMMISSION

Signed Paul A. Luthi (TECHNICIAN)

DATE 3-13-84

MAR 12 1984

INV. NO. 0731

CONSERVATION DIVISION
Wichita, Kansas

3-12-84