

1040154

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 057-20,390 - 0000

TECHNICIAN'S PLUGGING REPORT

SW NE SE , SEC. 31 , T 29 S, R 24 W/X  
1650 feet from ~~XXX~~ SE Corner of section line  
990 feet from ~~XXX~~ SE Corner of section line

Operator License # 5152

Lease Name Shelor Well # 2-31

Operator: Lee Banks  
Name & Address 200 West Douglas # 550  
Wichita, KS 67202

County Ford  
Well Total Depth 5385 175.01 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 644

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Rine Drilling Co. License Number 5654

Address 300 West Douglas, Suite 600, Wichita, KS 67202

Company to plug at: Hour: 5:00 pm Day: 6 Month: October Year: 19 84

Plugging proposal received from Lloyd Hubbard

(company name) Rine (phone) 316-267-1333

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1510' with 50 sx cement

2nd plug at 875' with 50 sx cement

3rd plug at 695' with 50 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with 10 sx cement.  
Plugging Proposal Received by Edgar M. Knobloch

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8:45 pm Day: 6 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1510' with 50 sx cement, 2nd plug at 875' with 50 sx cement, 3rd plug at 695' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
10-12-84  
OCT 12 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Buie

(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE 10-15-84

INV. NO. 4297

10-6

Signed *Edgar M. Knobloch*  
(TECHNICIAN)