

To: 1 051156  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5152

Operator: Lee Banks  
Name & Address 200 West Douglas, Suite 550  
Wichita, KS 67202

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2 p.m. Day: 12 Month: 4 Year: 19 89

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 5400' Perfs at 5292-97'

1st plug sand back to 5240' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 135 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 17 1989

4-17-89

Plugging Proposal Received by James R. Kapp  
(TECHNICIAN)

Plugging Operations Completed by Agent?: All  Part  None

Operations Completed: Hour: 5 p.m. Day: 12 Month: 4 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 5240' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 135 sx cement.

Maximum pressure 500 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2800' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

**INVOICED** (If not observed) observe this plugging.

DATE 4-24-89

INV. NO. 24440

4-12  
API NUMBER 15- 057-20,375 - 0000

SE SE SE, SEC. 31, T 29 S, R 24 W/E XX

330 feet from S section line

330 feet from E section line

Lease Name Shelor Well # 1

County Ford 175.50

Well Total Depth 5400 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 602

Signed Richard W. Lacey  
(TECHNICIAN)