

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-057 20,347-0000 ✓

CNW-54 Sec. 30, T 29S, R 24 W10

1980 feet from N(S) section line

660 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6029

Lease Name Denniston Well # 1-30

Operator: Ladd Petroleum Corp.
Name & Address P.O. Box 2848
Tulsa, Oklahoma
74101

County Ford

Well Total Depth 5500 feet 178.75

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 1/2" feet 1406

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Leben Drilling Co. License Number 5888

Address 640 Broadway Plaza Bldg. 1055, Broadway Wichita, Kans. 67202

Company to plug at: Hour: 3:45 AM, Day: 5 Month: January Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Byron Kelley

(company name) Ladd Petroleum Corp. (phone) _____

were: 1st plug @ 1460' w/ 50 sbx cement

2nd plug @ 930' w/ 40 sbx cement

3rd plug @ 40' to 0' on solid bridge w/ 10 sbx cement

Circulated 15 sbx cement in rat hole + 10 sbx cement in mouse hole;

Downell accomplished the plugging w/ 60/40 spgr w/ 2% gel +

3% CC.

Signed Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 3:45 AM, Day: 5 Month: January Year: 1984

ACTUAL PLUGGING REPORT This hole was plugged as proposed.

Remarks: _____

I hereby certify that the above plugging instructions were given as herein stated, and that I ~~did~~ / did not) observe this plugging.

INVOICED

RECEIVED STATE CORPORATION COMMISSION

Signed Paul A. Luthi ✓
(TECHNICIAN)

DATE 1-13-84

JAN 06 1984

FORM CP-2/3
Rev. 9-82

INV. NO. 90881W

CONSERVATION DIVISION
Wichita, Kansas