

1 050954
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Operator: Pickrell Drilling Company, Inc.
Name & Address 110 North Market, Suite 205
Wichita, KS 67202

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Pickrell Drilling Company, Inc. License Number 5123
Address 110 North Market, Suite 205, Wichita, KS67202

Company to plug at: Hour: 9 p.m. Day: 5 Month: 11 Year: 19 87

Plugging proposal received from Gary Christopher
(company name) Pickrell Drilling Company, Inc. (phone) 316-262-8427

were: to fill hole with heavy mud and spot cement through drill pipe
1st plug at 1540' with 50 sx cement, 2nd plug at 900' with 50 sx cement,
3rd plug at 570' with 40 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 10:45 p.m. Day: 5 Month: 11 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1540' with 50' sx cement,
2nd plug at 900' with 50 sx cement,
3rd plug at 570' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
I hereby certify that I have observed this plugging.

11-5-87
API NUMBER 15- 057-20,433-0000
SE SW SE, SEC. 30, T 29 S, R 24 W/E
330 feet from S section line
1650 feet from E section line
Lease Name Deniston Well # 1-C
County Ford 177.13
Well Total Depth 5450 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 550

Signed Richard W. Lacey
(TECHNICIAN)

DATE NOV 20 1987
INV. NO. 18917

RECEIVED
11-6-87
NOV 16 1987
CONSERVATION DIVISION
Wichita, Kansas

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date. 10 26 87 month day year

API Number 15-057-20,433-0000 yes

OPERATOR: License # 5123 Name Pickrell Drilling Company, Inc. Address 110 North Market, Suite 205 City/State/Zip Wichita, Kansas 67202 Contact Person Jay McNeil Phone (316) 262-8427

SE SW SE Sec 30 Twp 29 S, Rg 24 East West 330' Ft. from South Line of Section 1650' Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330' feet County Ford

CONTRACTOR: License # 5123 Name Pickrell Drilling Company, Inc. City/State Wichita, Kansas 67202

Lease Name Deniston Well # 1-C Ground surface elevation 257.8 feet MSL

Well Drilled For: XX Oil Storage Infield XX Gas Inj Pool Ext OWWO Expt XX Wildcat Cable

Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no

Depth to bottom of fresh water 110' 180 Depth to bottom of usable water 280' 430

Surface pipe by Alternates: 1 X 2 Surface pipe planned to be set 500+

IF OWWO: old well info as follows:

Operator Well Name Comp Date Old Total Depth

Conductor pipe required Projected Total Depth 5450 feet Formation Miss

I certify that well will comply with K.S.A. 55-101, et seq, plus eventually plugging hole to KCC specifications.

Date 10-22-87 Signature of Operator or Agent Title Chief Geologist

For KCC Use:

Conductor Pipe Required 4-22-88 feet; Minimum Surface Pipe Required 450 200 feet per Alt. 1 X

This Authorization Expires 4-22-88 Effective 10-27-87 Approved By 10-22-87

More in 10-26-87 set 8 5/8 @ 500'

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 3 columns: Plug depth (ft), Formation, and Plug size (SX). Rows include 1st plug @ 1500 ft, 2nd plug @ 1000 ft, 3rd plug @ 550 ft, 4th plug @ 40' w/S, and 5th plug @ ft.

(2) Rathole to surface minus 5 ft

(b) Mousehole to surface minus 5 feet

PUSHER Gary Christopher TD 5450 FORMATION MISS SURFACE PIPE 8 5/8 @ 550 ANHYDRITE ELEVATION STARTING TIME & DATE 9:00 AM COMPLETION TIME & DATE 10:45 PM 11/1/87 1st PLUG @ 1540 FT. WI 50 SX 2nd PLUG @ 1000 FT. WI 50 SX 3rd PLUG @ 570 FT. WI 40 SX 4th PLUG @ 40 FT. WI 10 SX RAT HOLE CIRCULATED WI 15 MOUSE HOLE CIRCULATED WI SX WATER WELL PLUGGED WI SX CEMENT COMPANY ALLIED TECHNICIAN

60/40 poz 6% Richard Witness Plugging

RECEIVED NOV 6 1987 CONSERVATION DIVISION Wichita, Kansas