

1 060622

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION E/2  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 057-20,406-0000  
E/2 E/2 SE, SEC. 33, T 29 S, R 23 W/4  
1300 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123 9747

Lease Name Birney Well # 1-E

Operator: Pickrell Drlg. Co.-Universal  
Name & Address Resources  
110 N. Market, Suite 205  
Wichita, KS 67202

County Ford 178.75  
Well Total Depth 5500 (Mississippi) feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 625

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pickrell Drilling Co. License Number 5123

Address Litwin Building, Suite 205, Wichita, KS 67202

Company to plug at: Hour: 8:00 pm Day: 20 Month: July Year: 19 85

Plugging proposal received from Gary Christopher

(company name) Pickrell (phone) 316-262-8427  
Elevation 2537 KB

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1494'

1st plug at 1500' with 50 sx cement

2nd plug at 950' with 50 sx cement

3rd plug at 650' with 50 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 10:00 pm Day: 20 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1500' with 50 sx cement, 2nd plug at 950' with 50 sx  
cement, 3rd plug at 650' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug  
at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15  
sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE AUG 01 1985

INV. NO. 9276

Signed Paul A. Luthi  
(TECHNICIAN)  
JUL 26 1985  
7-26-85

Wichita, Kansas