

11-23-87

To: 1 070473
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 057-20,108 - 10000

NW NW SE, SEC. 33, T 29 S, R 22 W/E
2310 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5236

Lease Name McFadden Well # 1

Operator: Plains Resources Inc.
Name & Address 1601 NW Expressway
Oklahoma City, OK 73118

County Ford 176.02

Well Total Depth 5416 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 281

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 11 a.m. Day: 20 Month: 11 Year: 19 87

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 5415' Perfs at 5294-5313'

1st plug pump 1 sx hulls and 20 sx cement to 5200',

2nd plug pump 50 sx cement at 1875', 3rd plug pump 50 sx cement at 940',

4th plug pump 50 sx cement at 310', 5th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2 p.m. Day: 23 Month: 11 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement to 5200',

2nd plug pumped 50 sx cement at 1875',

3rd plug pumped 50 sx cement at 940',

4th plug pumped 40 sx cement at 310',

5th plug pumped 10 sx cement at 40-0'.

RECEIVED
STATE CORPORATION COMMISSION

NOV 30 1987 11-30-87

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 2825' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

I (did / ~~xxxxxxx~~) observe this plugging.

DATE 12-4-87

Signed Dan Johnson (TECHNICIAN)

INV. NO. 19133

11-23