

To: 1 090757
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-057-20,463-0000
App. S/2 N/2 S/2, SEC. 33, T. 29 S, R. 22 W/2

TECHNICIAN'S PLUGGING REPORT
Operator License # 5123
Operator: Pickrell Drilling Company, Inc.
Name & Address 110 N. Market, Ste. 205
Wichita, KS 67202

11-13

1540 feet from S section line
2640 feet from E section line
Lease Name McFadden B Well # 1
County Ford 177.77
Well Total Depth 5470 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 515

Abandoned Oil Well _____ Gas Well _____ X Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____
Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 8:45 a.m. Day: 13 Month: 11 Year: 19 96
Plugging proposal received from James Ray

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

Work: 4 1/2" at 5415' w/150 sx cement, PBTD 5376', Perfs at 5300-15'
1st plug sand back to 5250' and dump .4 sx cement on top of sand through bailer,
2nd plug at 1550' with 50 sx cement,
3rd plug at 530' with 50 sx cement,
4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____
Operations Completed: Hour: 10:45 a.m. Day: 13 Month: 11 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 5250' and dumped 4 sx cement on top of sand through bailer,
2nd plug spotted 10 sx gel and 50 sx cement at 1550',
3rd plug pulled to 550' and spotted 5 sx gel and 50 sx cement,
4th plug pulled to 40' and spotted 10 sx cement. Stayed full.

11-14-96

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2800' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (the undersigned) observe this plugging.

INVOICED
DATE NOV 15 1996
INV. NO. 46984

Signed _____ (TECHNICIAN)